



Utility Engineering Consultants, *LLC*

Phone : 205.951.3838
FAX : 205.951.3839
WEB : www.uecllc.com

130 Southcrest Drive, Suite 100
Homewood, AL 35209
P.O. Box 19218
Birmingham, Alabama 35219

April 3, 2024

Columbiana Water Board
50 Water Works Street
Columbiana, Al 35051

**RE: ADDENDUM NO. 1
 COLUMBIANA WATER BOARD
 FIRE TOWER ROAD WATERLINE
 DWSRF PROJECT NO. FS010362-01
 CONTRACT NO. CB23 078**

All Contractors shall acknowledge receipt of Addendum No. 1 for the above referenced job by signing and returning this statement by email:dbrown@uecllc.com or fax to (205) 951-3839.

Contractor: _____

Received by: _____

Date: _____



Utility Engineering Consultants, LLC

Phone : 205.951.3838
FAX : 205.951.3839
WEB : www.uecllc.com

130 Southcrest Drive, Suite 100
Homewood, AL 35209
P.O. Box 19218
Birmingham, Alabama 35219

April 3, 2024

Columbiana Water Board
50 Water Works Street
Columbiana, Al 35051

**RE: ADDENDUM NO. 1
COLUMBIANA WATER BOARD
FIRE TOWER ROAD WATERLINE
DWSRF PROJECT NO. FS010362-01
CONTRACT NO. CB23 078**

The changes, modifications and/or additions covered by the set forth in this Addendum No. 1 shall become part of and be incorporated in the Specifications, Contract Documents and Bid Documents for the above referenced Project.

CONTRACT AND SPECIFICATIONS

- Section 00410 Proposal Form pages 3 and 4 shall be replaced with the attached Section 00410 pages 3 and 4 Addendum No. 1

This Addendum No. 1 shall be made a part of your set of Construction Contract Documents and Specifications. Acknowledgment of receipt of Addendum No. 1 shall be noted in the Bid for Unit Price Contracts Section of this contract.

Sincerely,

UTILITY ENGINEERING CONSULTANTS, LLC

Dave Bechtel, P. E.
DB/djb

ADDENDUM NO 1

**PROPOSAL FORM
BASE BID
COLUMBIANA WATER BOARD
FIRE TOWER ROAD WATERLINE REPLACEMENT
DWSRF PROJECT NO. FS010362-01
CONTRACT NO. CB23 078**

Contractor's Name _____

License # _____

Item No.	Description	Estimated Quantity	Bid Unit Price	Bid Price
1.	10" HDPE Pipe, Pressure DR9 Furnish and Install Complete Per LF	11,020 LF		
2.	Fire Hydrant Assembly Furnish and Install Complete Per EA	6 EA		
3.	10" Ductile Iron Fittings, Restrained Joints Furnish and Install Complete Per LB	25,000 LB		
4.	Pressure Reducing Vault Including Concrete Vaults, H2O Hatch, Excavation, Backfill, PRV, Pipe, Fittings and Connection to Water Line Furnish and Install Complete Per LS	2 LS		
5.	10" Gate Valve with 2" Operating Nut Valve Stem, Valve Box, Lid, and Valve Marker Furnish and Install Complete Per EA	20 EA		
6.	6" Gate Valve with 2" operating Not, Valve Stem, Valve Box, Lid and Valve Marker. Furnish and Install Complete Per EA	10 EA		
7.	Air Release Valve Assembly Furnish and Install Complete Per EA	4 EA		
8.	Wet Connection at Station 9+51.22 Including Tapping, Equipment and Material to Connect to Existing 6" Main. Furnish and Install Complete Per LS	1 LS		
9.	Wet Connection at Station 38+55.8 Including Tapping Sleeve and Valve, All Labor, Equipment and Material to Connect to Existing 6" Main. Furnish and Install Complete Per LS	1 LS		

ADDENDUM NO 1

Item No.	Description	Estimated Quantity	Bid Unit Price	Bid Price
10.	Wet Connection at Station 87+45 including Tapping Sleeve and Valve, all Labor, Equipment and Material to Connect to New 10" Main, excludes PRV Furnish and Install Complete Per LS	1 LS		
11.	ALDOT #78 Stone for Driveway Replacement Per Ton	200 Ton		
12.	Class A Concrete 4" Thick Including Wire Mesh to Replace Cut Concrete Drives Furnish and Install Complete Per SY	200 SY		
13.	Rip Rap, ALDOT Class I, Installed in Drainage Ditch as Required Furnish and Install Complete Per Ton	500 Tons		
14.	Cleanup and Seeding of Right-of-Way Furnish and Install Complete Per LF	6,400 LF		
15.	Service Line ¾" Munipex Pipe Installed on Main Line Side of Road Furnish and Install Complete Per EA	3 EA		
16.	Service Line ¾" Municipex in 2" Casing Pipe Bored Under Road to Meter. Furnish and Install Complete Per EA	5 EA		
TOTAL BASE BID				